

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-26346-00-00
Spot: NWNESENW Sec/Twnshp/Rge: 8-15S-19W
3837 feet from S Section Line, 2976 feet from E Section Line
Lease Name: DINGES FAMILY Well #: 1
County: ELLIS Total Vertical Depth: 3704 feet

Operator License No.: 4787
Op Name: TDI, INC.
Address: 1310 BISON RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3702		150 SX
SURF	8.625	213		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/30/2017 8:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: BRETT HILDERBRAND Company: TDI, INC. Phone: (785) 871-7311

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 19 sx gel and 600 # hulls.
Perforations: 3365' - 3369', 3421' - 3425' and 3500' - 3502'.
DV Tool: 1266' w/155 sx cement.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/30/2017 11:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service ran in hole with tubing to 3350'. Quality rigged to tubing and pumped 8 bbl water followed by 14 sx gel, followed by 50 sx cement w/300 # hulls mixed in. Pulled tubing to 1663'. Rigged to tubing and pumped 160 sx cement w/250 # hulls mixed in to circulate cement up 5 1/2" casing. Pulled tubing. Topped off 5 1/2" casing with 20 sx cement. Hole standing full. Rigged to 8 5/8" surface casing with instant pressure to 200 psi.

GPS: 38.76530 -099.45933

Perfs:

Top	Bot	Thru	Comments
3500	3502		
3421	3425		
3365	3369		

INVOICED
OCT 12 2017

Remarks: QUALITY OIL WELL CEMENTING TICKET # 373

Plugged through: TBG

District: 04

Signed _____


(TECHNICIAN)

CJM

KCC WICHITA

SEP 28 2017

RECEIVED

SEP 21 2017

Form CP-2/3