

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-26483-00-00
Spot: NENWSWSE Sec/Twnshp/Rge: 11-15S-19W
1220 feet from S Section Line, 2025 feet from E Section Line
Lease Name: URBAN UNIT Well #: 1
County: ELLIS Total Vertical Depth: 3724 feet

Operator License No.: 4787
Op Name: TDI, INC.
Address: 1310 BISON RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3707		150 SX
SURF	8.625	222		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/11/2017 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: BRETT HILDERBRAND Company: TDI, INC. Phone: (785) 871-7311

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement, 14 sx gel and 600 # hulls.
DV Tool at 1285' w/155 sx cement.
Perforations: 3650' - 3652', 3394' - 3396', 3370' - 3372' and 3345' - 3348'

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/11/2017 11:15 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service ran in hole with tubing to 3324'. Quality rigged to tubing and pumped 8 bbl water followed by 14 sx gel, followed by 50 sx cement w/250 # hulls mixed in. Pulled tubing to 1658'. Quality rigged to tubing and pumped 195 sx cement w/250 # hulls to circulate cement to surface. Pulled tubing. Topped off 5 1/2' casing with 60 sx cement. Hole standing full. Rigged to 8 5/8" surface casing and pumped 5 sx cement w/200 psi. Shut in pressure 200 psi.

GPS: 38.75821 -09940056

Perfs:


Top	Bot	Thru	Comments
3394	3396		
3370	3372		
3345	3348		

Remarks: QUALITY OILWELL CEMENTING TICKET # 381

Plugged through: TBG

District: 04

Signed
KCC WICHITA


(TECHNICIAN)

CM

SEP 28 2017

RECEIVED

SEP 12 2017

Form CP-2/3

INVOICED

OCT 12 2017