

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-21865-00-01
Spot: S2SWSW Sec/Twnshp/Rge: 25-16S-27W
375 feet from S Section Line, 4581 feet from E Section Line
Lease Name: MCBEE C Well #: 1-25
County: LANE Total Vertical Depth: 4650 feet

| Operator License No.: <u>9408</u> | String | Size | Depth (ft) | Pulled (ft) | Comments |
|---|--------|-------|------------|-------------|-----------------|
| Op Name: <u>TRANS PACIFIC OIL CORPORATION</u> | DVT | 4.5 | 2135 | | WITH 325 SX CMT |
| Address: <u>100 S MAIN STE 200</u> | PROD | 4.5 | 4622 | 0 | WITH 225 SX CMT |
| <u>WICHITA, KS 67202</u> | SURF | 8.625 | 314 | | WITH 185 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/21/2017 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Revd. from: MONTE BOYDSTON Company: TRANS PACIFIC OIL CORPORATO Phone: (316) 262-3596

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 40 SX CMT & 200# HULLS. SPACER TO 2150'. CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/21/2017 11:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4100' & PUMPED 40 SX CMT & 200# HULLS. PULL TBG TO 2165' & PUMPED 175 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 15 SX CMT. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4145 | 4149 | | |
| 4060 | 4066 | | |

INVOICED
OCT 12 2017

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier
(TECHNICIAN)

SA

RECEIVED
SEP 26 2017
KCC DODGE CITY