

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-24984-00-00
Spot: SESWSNW Sec/Twnshp/Rge: 34-20S-13W
2500 feet from N Section Line, 1890 feet from W Section Line
Lease Name: HISS ADAMS Well #: 1
County: BARTON Total Vertical Depth: 3647 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3640		145 SX
SURF	8.625	333		300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/01/2017 10:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: KEN BUEHLER Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement and 400 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/01/2017 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1300', 730' and 300'. Ran tubing to 3220' and pumped 14 sx gel followed by 70 sx cement w/200 # hulls. Pulled tubing to 1703' and pumped 60 sx cement w/200 # hulls. Pulled tubing to 730' and pumped 50 sx cement. Pulled tubing to 300'. Circulated cement to surface on casing with 40 sx cement. Circulated cement to surface on surface pipe with 50 sx cement.

GPS: 38.26857 -098.74947

Perfs:

Top	Bot	Thru	Comments
3550	3554		
3454	3458		
3427	3431		
3412	3416		
3304	3309		
3298	3301		
3290	3298		
3268	3273		

INVOICED
OCT 12 2017

Remarks: QUALITY OILWELL CEMENTING

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

KCC WICHITA

SEP 28 2017

RECEIVED

SEP 07 2017