

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19650-00-00
Spot: S2SWNWNE Sec/Twnshp/Rge: 22-25S-5E
4271 feet from S Section Line, 2321 feet from E Section Line
Lease Name: PORTER C Well #: 1
County: BUTLER Total Vertical Depth: 2597 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 2596 | | 95 SX |
| SURF | 8.625 | 217 | | 135 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/25/2017 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: _____ Phone: (316) 682-1537

Proposed Plugging Method: AS PER KCC RULES & REGS/ 50 SXS @ 2540', PERF AND CIRCULATE

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/25/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TUBING @ 2435', QES EST. CIRCULATION, MIXED & PUMPED 50 SXS CLASS A 3% AND 40# HULLS AND DISPLACED IN CASING. TAGGED CEMENT PLUG @ 2087'. LOADED HOLE & PRESSURE TESTED CASING/ HELD OK. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES 250'-251' (4 SHOTS). SWEDGED INTO CASING, QES MIXED & PUMPED 110 SXS 60/40 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET # 54669.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2543 | 2546 | | CSG |
| 2426 | 2434 | | CSG |

Remarks: COMPLIANCE DENIED TA

Plugged through: TBG

INVOICED
OCT 12 2017

District: 02

Signed Jeff Kulack DISTRICT SUPERVISOR
(TECHNICIAN)