

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-22546-00-01  
Spot: N2NESW Sec/Twnshp/Rge: 28-33S-13W  
2310 feet from S Section Line, 1980 feet from W Section Line  
Lease Name: SPRIGGS G Well #: 1  
County: BARBER Total Vertical Depth: 4099 feet

Operator License No.: 33168  
Op Name: WOOLSEY OPERATING COMPANY, LL  
Address: 125 N MARKET STE 1000  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3650		WITH 2 SX CMT
PROD	4.5	4128	1214	WITH 160 SX CMT
SURF	10.75	210		WITH 175 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/07/2017 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: BILL GALLAUGHER Company: WOOLSEY OPERATING Phone: (620) 886-5606

Proposed Plugging Method: CIBP @ 3650' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 250' WITH 70 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE  
Date/Time Plugging Completed: 09/07/2017 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SET CIBP @ 3650' & TOP WITH 2 SX CMT. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 250' WITH 70 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT. TOP OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3877	3887		
3673	3679		

INVOICED  
OCT 12 2017

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed \_\_\_\_\_

*Ken Jehlik*  
SAE  
(TECHNICIAN)

RECEIVED  
SEP 14 2017  
KCC DODGE CITY

*MD*