

1080213

15.185.12905.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 4-17-53

TECHNICIAN'S PLUGGING REPORT

SW NW SE , SEC. 22 , T 21 S, R 12 W/X
1650 N SE Corner of
feet from ~~XXX~~ section line
W SE Corner of
2310 feet from ~~XXX~~ section line

Operator License # 5354

Lease Name Rose Well # 5

Operator: Southern States Oil Co.

County Stafford

Name & Address Box 1365

Well Total Depth 3583 116.45 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 282

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:00 am Day: 17 Month: September Year: 19 84

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 3581 Perfs 3422-28'

1st plug sand back to 3370' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement

Plugging Proposal Received by J. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 pm Day: 17 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 3581' Perfs at 3422-28'

1st plug sanded back to 3370' and dumped 5 sx cement on top of sand through bailer

2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in pressure 150 psi

RECEIVED
STATE CORPORATION COMMISSION
SEP 24 1984

Remarks: They recovered 1800' 5 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc
(if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
I (did / did not) observe this plugging.

Signed J. H. Metz
(TECHNICIAN)

DATE 10-1-84

INV. NO. 3931