

To: 1052129 5-6
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-Drilled 1950 15.185.00996.0000
SW NE NE, SEC. 22, T 21 S, R 12 W/EX
4290 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 31647
Operator: K.C. Operations
Name:
Address RR 2, Box 113
Ellinwood, KS 67526

Lease Name Taylor Well # 3
County Stafford 116.71
Well Total Depth 3591 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 285

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Quality Well Service, Inc. License Number 31925
Address 249 E. Beth Dr., Sterling, KS 67579

Company to plug at: Hour: 3 p.m. Day: 6 Month: 5 Year: 19 97

Plugging proposal received from Richard McIntyre
(company name) Quality Well Service, Inc. (phone) 316-727-3410

were: 5 1/2" at 3564', Perfs at 3330-38, 3380-85, 3413-19, 3260-3300'
1st plug sand back to 3200' and dump 5 sx cement on top of sand through bailer,
2nd plug spot 50 sx cement at 620',
3rd plug spot 50 sx cement at 300',
4th plug spot 10 sx cement at 40'.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:30 p.m. Day: 6 Month: 5 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3085' and dumped 5 sx cement on top of sand through bailer,
2nd plug pumped 5 sx gel and 50 sx cement at 620',
3rd plug pulled to 310' with 50 sx cement,
4th plug pulled to 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1580' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form)

INVOICED
DATE MAY 14 1997
INV. NO. 48113

Signed Richard M. Taylor
(TECHNICIAN)

RECEIVED
MAY 14 1997
MAY 14 1997
MAY 14 1997