

10522610

TO: STATE CORPORATION COMMISSION

5-27

API NUMBER 15-185-22'371.0000
NW SE NW , SEC. 22 , T 21 S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION 3630 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3630 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME LONG WELL # 2

TECHNICIAN'S PLUGGING REPORT COUNTY STAFFORD

OPERATOR LICENSE # 31164 WELL TOTAL DEPTH 3700' 120.25 FEET

OPERATOR: DOUBLE B OIL CO. PRODUCTION CSG: SIZE 4 1/2" FEET 3695'

NAME AND ADDRESS 389 GROVE TERRACE SURFACE CASING: SIZE 8 5/8" FEET 259'

ADDRESS GREAT BEND, KS 67530

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE, INC. LICENSE NUMBER 31925

ADDRESS 249 BETH DRIVE, STERLING, KS 67579-9048

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 27 MONTH: MAY YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE INC (PHONE) 316-727-3410

WERE: PERFORATIONS 3564'-3570' 3580'- 3584 3606'-3612'

SAND BOTTOM TO 3500' AND PLACE 4 SX OF CEMENT ON TOP OF THE SAND WITH DUMP BAILOR

SPOT PLUGS THROUGH CASING WHILE PULLING PIPE.

1ST PLUG AT 670' WITH 10 SX OF GEL FOLLOWED BY 50 SX OF CEMENT.

2ND PLUG AT 290' WITH 40 SX OF CEMENT. 3RD PLUG AT 40' WITH 10 SX OF CEMENT.

RECOMMENDED 60/40 POZMIX 6% GEL PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:35 AM DAY: 27 MONTH: MAY YEAR: 1998

ACTUAL PLUGGING REPORT SANDED BOTTOM TO 3500' AND PLACED 4 SX OF CEMENT ON TOP OF SAND.

PUMPED PLUGS THROUGH CASING WHILE PULLING PIPE.

1ST PLUG AT 670' WITH 10 SX OF GEL FOLLOWED BY 50 SX OF CEMENT

2ND PLUG AT 290' WITH 40 SX OF CEMENT,

3RD PLUG AT 40' WITH 10 SX OF CEMENT

GOOD CIRCULATION THROUGH OUT THE PLUG JOB.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED RECOVERED 2630' OF 5 1/2" CASING
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED

SIGNED Richard M. Lacey (TECHNICIAN) FORM CP-2/3

DATE 6-8-98

INV. NO. 50680

RECEIVED

KANSAS CORPORATION COMMISSION

JUN 03 1998

CONSERVATION DIVISION WICHITA, KS