

1052396

TS: STATE CORPORATION COMMISSION

API NUMBER 15-185-22,335.0000
NW SW SW SEC. 11, T 21 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4950 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME FISCHER WELL # 8

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD 117.78

OPERATOR LICENSE # 6039 6/5

WELL TOTAL DEPTH 3630 FEET

OPERATOR: L.D. DRILLING, INC. PRODUCTION CSG: SIZE 5 1/2" @ 3630' WITH 150 SX

NAME AND RR 1, BOX 183 B SURFACE CASING: SIZE 8 5/8" @ 727' WITH 285 SX

ADDRESS GREAT BEND, KS 67530

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DS&W WELL SERVICING LICENSE NUMBER 6901

ADDRESS PO BOX 231 CLAFLIN, KS 67525

COMPANY TO PLUG AT: HOUR: 12:00 PM DAY: 05 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM BRIAN

(COMPANY NAME) DS&W WELL SERVICING (PHONE) 316-587-3361

WERE: PERFS AT 3530-3536

1ST PLUG SAND TO 3480' AND 5 SX CEMENT. 2ND PLUG AT 760' WITH 10 SX GEL & 50 SX CEMENT.

3RD PLUG AT 300' WITH 40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:00 PM DAY: 05 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT

1ST PLUG SAND TO 3480' AND 5 SX CEMENT. 2ND PLUG AT 760' WITH 10 SX GEL & 50 SX CEMENT.

3RD PLUG AT 300' WITH 40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

RECEIVED STATE CORPORATION COMMISSION JUN 8 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1800' OF 5 1/2" CASING.

CONSERVATION DIVISION Wichita, Kansas

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING

INVOICED

SIGNED Richard W. Lacey

DATE 6/9/00

(TECHNICIAN) FORM CP-2/3

INV. NO. 61847

Handwritten initials and a circled 'K'.