

10-14-87 15.185.13255.0000

To: 1 120032
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA

NW NW NE, SEC. 36, T 21 S, R 13 W/4
4950 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5337

Lease Name Fischer Well # C-1

Operator: Nadel and Gussman
Name & Address 3232 First National Tower
Tulsa, OK 74103

County Stafford 118.17
Well Total Depth 3636 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 320

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Company License Number NA

Address Box 31, Russell, KS 67665

Company to plug at: Hour: 10 a.m. Day: 14 Month: 10 Year: 1987

Plugging proposal received from Frank Neff

(company name) Nadel and Gussman (phone) 918-583-3333

were: 5 1/2" at 3634' Open hole 3634-3636'
1st plug pump 200 lbs. hulls and 300 sx ATL cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 14 Month: 10 Year: 1987

ACTUAL PLUGGING REPORT 1st plug pumped into 5 1/2" casing with 150 sx lite cement, mixed 250 lbs. hulls with cement,

2nd plug pumped 150 sx lite cement into annulus between 5 1/2" and 8 5/8" casing, mixed 100 lbs. hulls in first part of cement.

8 5/8" - Pumping pressure 450-500 psi and shut in 200 psi.

5 1/2" - pumping pressure 450-500 psi and shut in 200 psi.

OCT 21 1987
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Used lite cement by Allied. No recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED
(If additional description is necessary, use BACK of this form.)
I (and my agent) observe this plugging.

DATE 10-22-87

Signed Duane Rankin (TECHNICIAN)

INV. NO. 18621