

To: 1 060653
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,268-0000
SW NW SW, SEC. 36, T 21 S, R 13 W EX
1650 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039
Operator: L. D. Drilling, Inc.
Name & Address R. R. 1, Box 183-B
Great Bend, KS 67530

Lease Name Hayden Well # 1
County Stafford 120.28
Well Total Depth 3701 (Arbuckle 10') feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor L. D. Drilling, Inc. License Number 6039
Address R. R. 1, Box 183-B, Great Bend, KS 67530

Company to plug at: Hour: 2:00 pm Day: 30 Month: August Year: 19 85

Plugging proposal received from Don Pope

(company name) L. D. Drilling (phone) 316-793-3051
Elevation 1874 GL
were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 710-28'

- 1st plug at the Arbuckle if penetrated 50' or more with 40 sx cement
- 2nd plug at 730' with 50 sx cement
- 3rd plug at 330' with 50 sx cement
- 4th plug hulls - plug at 40' -- cement to surface with 10 sx cement
- 6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:30 pm Day: 30 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 740' with 50 sx cement, 2nd plug at 330' with 50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 6 1985

Remarks: Used 60/40 Pozmix 6% gel by Halliburton
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
did not observe this plugging.

Signed Paul A. Luthi (TECHNICIAN)

DATE SEP 10 1985

INV. NO. 9913