

8-9-88

6 020474

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 051-24,563.00.00

NE SW NE, SEC. 34, T 12 S, R 16 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5652

Operator: Mustang Co. Inc.

Name & Address: Great Bend, Ks. 67530

3630 feet from S section line

1650 feet from E section line

Lease Name Froelich F Well # 7

County Ellis 115.86

Well Total Depth 3565 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 266

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Western Ks. Drilling License Number 4083

Address _____

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Bill Nelson

(company name) _____ (phone) _____

Order 195 sks 60/40 Poz 6% Gel 3% Ca Cl 1 sk F.C. and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs with good circulation and no fluid loss.

Plugging Proposal Received by Gilbert Balthazor (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour 1:15 PM Day 9 Month August Year 19 88

ACTUAL PLUGGING REPORT

1st plug at 3450' w/25 sks

2nd plug at 1230' w/25 sks

3rd plug at 710' w/80 sks

4th plug at 270' w/40 sks

5th plug at 40' w/10 sks

RECEIVED STATE CORPORATION COMMISSION

AUG 30 1988

CONSERVATION DIVISION Wichita, Kansas

Remarks: 15 sks in rat hole Allied Cement

(If additional description is necessary, use BACK of this form.)

INVOICED (Agent did not observe this plugging.)

DATE 8-31-88

Signed Gilbert Balthazor (TECHNICIAN)

NO. 22068