

6 070749

153  
2-23 051.24563.00.01 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- OWWO  
NE SW NESEC. 34, T 12 S, R 16 W/E

3630 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
6600  
Operator License # \_\_\_\_\_

Lease Name Froelich Well # 1 OWWO  
County Ellis 40.43

Operator: Don Karst Well Service  
Name & Address 201 East 29th St.  
Hays, Ks. 67601  
Don Karst

Well Total Depth 1244 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 266

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A   
Other well as hereinafter indicated \_\_\_\_\_ OWWO Hit Cement Plug Went out of Hole.

Plugging Contractor Emphasis Oil Operations License Number \_\_\_\_\_  
Address Box 506 4th Kansas, Russell, Ks. 67665

Company to plug at: Hour: PM Day: 23 Month: Feb Year: 19 89

Plugging proposal received from Tom Alm

(company name) Emphasis (phone) \_\_\_\_\_

were: 8 5/8" - 266' cwc w/NA. Ely. 2042' Anhy 1189' No Arb. Mud condition, 50 vis.

9.9 weight; Proposal: 190 sks 60/40 Poz 6% Gel 3% Cal Cl. Spot with drill stem. Circulate heavy mud between all plugs. 25 sks at 1230'; 100 sks at 710'; 40 sks at 300'; 10 sks at 40'.  
15 sks in rathole (cir)

Plugging Proposal Received by Marion J. Schmidt  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 8:30PM Day: 23 Month: Feb Year: 19 89

ACTUAL PLUGGING REPORT Ordered 190 sks 60/40 Poz 6% Gel 3% Cal Cl.

Spotted with drill stem. Circ heavy mud betwen all plugs. 1st plug at 1230' w/25 sks cement. 2nd plug at 710' w/100 sks w/1 F.C. 3rd plug at 300' w/40 sks cement.

15 sks rathole (cir)

RECEIVED  
STATE CORPORATION COMMISSION

MAR 07 1989

Remarks: \_\_\_\_\_  
(if additional description is necessary, use BACKSEALING DIVISION (TECHNICIAN) Wichita Kansas)

INVOICED

DATE 3-7-89

INV. NO. 24073

Signed Marion J. Schmidt  
(TECHNICIAN)  
Marion J. Schmidt