

15.083.20033.0000

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

DEC 26 1967

CONSERVATION DIVISION  
Wichita, Kansas

12-26-1967

Dear Sir:

Mr. Williams of Rockford Mineral Products has this date requested permission to plug the following described well:

Mr. Williams guarantees payment of the plugging fee.

Operator's full Name: Rockford Mineral Products Inc.

Complete Address: 206 W. State St., Rockford, Illinois

Lease Name: Ploger Well No. 1

Location: SW SE Sec. 10 Twp. 21 Rge. 25 XX (E) (W)

County Hodgeman Total Depth 4895' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Williams was instructed to plug the well as follows:

- 8 5/8" to 280' circulated w/ cement. Mud 4895' to 900'
- Spotted 100 sacks cement 900' to 550' Mud 550' to 280'
- Spotted 30 sacks cement 280' to 180' Mud 180' to 45'
- Plug, Hulls & 15 sacks cement 45' to 0'

Very truly yours,

Edgar J. Evers  
Conservation Division Agent