



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202  
RECEIVED  
WICHITA CORPORATION COMMISSION

SEP 4 1914

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Dreiling of Sutton has this

date requested permission to plug the following described well:

Mr. Dreiling guarantees payment of the plugging fee.

Operator's full Name: O.A. Sutton

Complete Address: 800 Sutton Place, Wichita, Kansas

Lease Name: Sinclair Well No. 1A

Location: SW SW Sec. 9 Twp. 21 Rge. 25 (E) (W)

County: Hodgeman Total Depth 4470' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Dreiling was instructed to plug the well as follows:

8 5/8" to 553' circulated w/ cement. Mud 4470' to 570'

Spot 35 sacks cement 570' to 470' Mud 470' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent