

State of Kansas



15.113.70625.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

March 2, 1979

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Willard Brucker of Blackstone Drilling Inc. has this date requested permission to plug the following described well:

Mr. Brucker guarantees payment of the plugging fee.

Operator's full Name: John J. Darrah, Jr.

Complete Address: 1010 Century Plaza Bldg, Wichita, Kansas 67202

Lease Name: Moundridge Townsite #2 (U.S.D #423) Well No. 2

Location: 70' W. of SE SE SW Sec. 23 Twp. 21 Rge. 2 (E) (W) X

County: McPherson Total Depth 3369 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Brucker was instructed to plug the well as follows:

Fill hole with mud to 130'. Push plug and 1/4 sack hulls to 130' and cement hole with 15 sacks cement.

Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement.

Bridge rat hole and cement with 2 sacks cement.
8 5/8" - 130' cement circulated.

RECEIVED
STATE CORPORATION COMMISSION

MAR 8 1979

Very truly yours,

CONSERVATION DIVISION
Wichita, Kansas

Albert J. Loman
Conservation Division Agent