



15.113.20660.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

September 1, 1979

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP - 6 1979
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Willard Brucker of Blackstone Drilling Inc. has this date requested permission to plug the following described well:

Mr. Brucker guarantees payment of the plugging fee.

Operator's full Name: Royce Graber and John J. Darrah, Jr.

Complete Address: 1010 Century Plaza Bldg., Wichita, Ks. 67202

Lease Name: Stucky-Graber Well No. 1

Location: NW SE SW Sec. 23 Twp. 21 Rge. 2 (W) X

County: McPherson Total Depth 3358' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Brucker was instructed to plug the well as follows:

8 3/8" - 126' - cement circulated. Fill hole with mud to 120'.
Push plug and 1/4 sack hulls to 120' and cement hole
with 20 sacks cement. Fill hole with mud to 40'.
Push plug and 1/2 sack hulls to 40' and cap hole with
10 sacks cement. Bridge rathole and cement with 2 sacks.

Very truly yours,

Arthur J. Lorenz
Conservation Division Agent