

State of Kansas



15.083.20421.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027

3830 S. Meridian

WICHITA, KANSAS 67217

VERBAL PERMIT FORM

RECEIVED

(To Be Filed By Plugging Agent) STATE CORPORATION COMMISSION

Intention to drill
March 14, 1975. 15-083-20421

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

3-28-1975

Dear Sir:

Mr. Lester Ingalls of Slawson Drilling has this date requested permission to plug the following described well:

Mr. Ingalls guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson

Complete Address: 408-120 Bldg, Wichita, Kans

Lease Name: Soren "A" Well No. # 1

Location: C. N. W. N.W. Sec 33 Twp. 21 Rge. (E) (W) 24

County: Hodgeman Total Depth 4646 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ingalls was instructed to plug the well as follows:

There was 569 ft of 8 1/2" surface casing
Cement Circulated. 1st plug at 850 ft with
50 sacks of 50-50 pos mix + 6% gel. Fill with
heavy mud to 600 ft. 2nd plug 600 ft with 35
sacks of 50-50 pos mix + 6% gel. Fill with heavy
mud to 400 ft. 3rd plug
40-0 with 10 sacks 50-50 pos
mix + 4% gel. 2 sacks in
mat hole

Very truly yours,

Clarence J. Thomas
Conservation Division Agent