



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg.
 WICHITA, KANSAS 67202

STATE RECEIVED
 CORPORATION COMMISSION
 DEC 20 1968
 CONSERVATION DIVISION
 212 N. Market
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

December 17, 1968

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Dick Mead of Sterling Drilling Company has this date requested permission to plug the following described well:

Mr. Mead guarantees payment of the plugging fee.

Operator's full Name: Beacon Resources Corporation

Complete Address: 312 Union Center Bldg., Wichita, Kansas 67202

Lease Name: Dyck Well No. 2

Location: NW NW SE Sec. 13 Twp. 21 Rge. 2 (E)(W) X

County: Mc Pherson Total Depth 3492' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mead was instructed to plug the well as follows:

Fill hole with mud to 200'. Push plug and 1/4 sack hulls to 200' and
cement hole with 25 sacks through drill pipe. Fill hole with mud to
40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks
cement. Bridge rathole and cement with 2 sacks.

Very truly yours,


 Conservation Division Agent