



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

December 31, 1968

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dick Mead of Sterling Drilling Company has this date requested permission to plug the following described well:

Mr. Mead guarantees payment of the plugging fee.

Operator's full Name: Beacon Resources Corporation

Complete Address: 312 Union Center Bldg., Wichita, Kansas 67202

Lease Name: Nightingale Well No. 1

Location: SE NE SW Sec. 13 Twp. 21 Rge. 2 ~~(E)~~ (W) X

County: Mc Pherson Total Depth 3374' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mead was instructed to plug the well as follows:

Fill hole with mud to 200'. Push plug and 1/4 sack hulls to 200' and cement

hole with 25 sacks cement through drill pipe. Fill hole with mud to 40'.

Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement.

Bridge rathole and cement with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 3 1969
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

Conservation Division Agent