



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

June 29, 1970

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 2 1970
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Dick Mead of Sterling Drilling Company has this date requested permission to plug the following described well:

Mr. Mead guarantees payment of the plugging fee.

Operator's full Name: F. G. Holl

Complete Address: 6427 E. Kellogg, Wichita, Kansas

Lease Name: Dresbach Well No. 1-B

Location: C E/2 SE NE Sec. 7 Twp. 21 Rge. 6 (N) (W) X

County: Rice Total Depth 190' Oil Well
OWWO

Gas Well Input Well SWD Well D & A Lost Hole X

Mr. Mead was instructed to plug the well as follows:

Push plug and 1/2 sack hulls to 190' and cement hole with 35 sacks cement
through drill pipe. Push plug and 1/2 sack hulls to 40' and cap hole with
10 sacks cement. Bridge rathole and cement with 2 sacks cement.

(Iron in hole at 190'--unable to drill out.)

Very truly yours,


Conservation Division Agent