

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-30368-00-00
Spot: SENWSE Sec/Twnshp/Rge: 10-15S-15W
1650 feet from S Section Line, 1650 feet from E Section Line
Lease Name: BLEHM Well #: 2
County: RUSSELL Total Vertical Depth: 3300 feet

Operator License No.: 3134 String Size Depth (ft) Pulled (ft) Comments
Op Name: MORRIS, TERRY E. DBA G L M COMPA PROD 5.5 3300 125 SX
Address: PO BOX 193 SURF 8.625 148 135 SX
RUSSELL, KS 67665

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/07/2017 10:30 AM
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.
Proposal Rcvd. from: TODD L. DINKEL Company: MORRIS, TERRY E. DBA G L M CO Phone: (785) 639-5415

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/07/2017 6:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1450' and 857'. Casing leak in the Dakota zones. Ran tubing to 3135' and pumped 150 sx cement w/200 # hulls in the last half of cement. Pulled tubing to 1650' and pumped 125 sx cement w/200 # hulls. Pulled to tubing to 479' and pumped 70 sx cement. Circulated cement to pit. POOH. Hooked to braden head and pumped 30 sx cement at 250 psi. Shut in pressure 250 psi. Hooked to casing and pumed 5 sx cement at 350 psi. Shut in. 09/08/2017 - Cement down less than 20'.

GPS: 38.75918 -09897240

Perfs:

Top	Bot	Thru	Comments
3265	3269		
3251	3255		
3216	3222		
3199	3202		
3177	3183		
3153	3158		
3077	3079		
3064	3066		

INVOICED
OCT 17 2017

Remarks: GLOBAL CEMENTING SERVICE TICKET # 3086

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

KCC WICHITA

SEP 12 2017

SEP 28 2017

RECEIVED