

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-153-21141-00-00  
Spot: S2SENEWSW Sec/Twnshp/Rge: 24-1S-36W  
1380 feet from S Section Line, 2310 feet from W Section Line  
Lease Name: JOHN 'A' Well #: 1-24  
County: RAWLINS Total Vertical Depth: 4776 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4769		450 SX
SURF	8.625	268		185 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/30/2017 9:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 443-1031

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 1500 # gel and 250 # hulls.  
8 5/8" surface casing set at 268' w/185 sx cement.  
5 1/2" production casing set at 4769' w/450 sx cement. Bond log indicates cement at surface.  
TD 4776'. PBTD 4735'.  
Perforations: 4414' - 4423'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/30/2017 12:30 PM KCC Agent: DARREL DIPMAN

**Actual Plugging Report:**

Ran tubing to 4374' and pumped 1500 # gel followed by 60 sx cement w/250 # hulls. Pulled tubing to 3207' and pumped 50 sx cement. Pulled tubing to 2462' and pumped 120 sx cement. Pulled tubing to 1231' and pumped 130 sx cement. Cement circulated to surface. Pulled tubing to surface. Connected to 5 1/2" casing and pumped 15 sx cement. Connected to 8 5/8" surface casing and pumped 15 sx cement.

GPS: 39.94831N -101.30940W

**Perfs:**

Top	Bot	Thru	Comments
4414	4423		

INVOICED  
OCT 11 2017

Remarks: HURRICANE SERVICES INC. TICKET # 100794

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN) *CM*

KCC WICHITA  
SEP 28 2017  
RECEIVED

SEP 07 2017