

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-22279-00-00
Spot: N2N2SESE Sec/Twnshp/Rge: 12-15S-22W
1030 feet from S Section Line, 660 feet from E Section Line
Lease Name: SCHMIDT Well #: 1-12
County: TREGO Total Vertical Depth: 4252 feet

Operator License No.: 31652
Op Name: NORSTAR PETROLEUM, INC.
Address: 88 INVERNESS CIR E. UNIT F104
ENGLEWOOD, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4247		125 SX
SURF	8.625	217		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/01/2017 9:30 AM
Plug Co. License No.: 35052 Plug Co. Name: HUSKER ENERGY SERVICES, INC.
Proposal Rcvd. from: DUANE MORGAN Company: NORSTAR PETROLEUM, INC. DBA Phone: (785) 798-0934

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls and 21 sx gel.
CIBP set at 4105'.
Port Collar set at 1627' w/175 sx cement.
Perforations: 4122' - 4139'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/01/2017 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 5075' and pumped 21 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1699' and pumped 175 sx cement. Cement circulated. Pulled tubing. Topped off casing with 15 sx cement. Tied on to backside and squeezed with 25 sx cement. Shut in pressure 300 psi.

GPS: 38.75758 -099.71083

Perfs:

Top	Bot	Thru	Comments
4128	4134		
4122	4124		


INVOICED
OCT 11 2017

Remarks: SWIFT CEMENT TICKET # 30665

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

CM

KCC WICHITA

SEP 28 2017

RECEIVED

SEP 07 2017