

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-22039-00-00
Spot: SENENENW Sec/Twnshp/Rge: 17-34S-32W
392 feet from N Section Line, 2346 feet from W Section Line
Lease Name: COPE Well #: 17 1
County: SEWARD Total Vertical Depth: 6092 feet

Operator License No.: 34904
Op Name: PALMER OIL, INC.
Address: 3118 N. CUMMINGS RD. PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5910		WITH 2 SX CMT
PROD	5.5	6077	2000	WITH 160 SX CMT
SURF	8.625	1676		WITH 530 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/07/2017 11:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: OCTAVIO D MORALES Company: PALMER OIL Phone: (620) 275-2963

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS WITH 2 SX CMT. PLUG AT 1720' WITH 15 SX GEL & 50 SX CMT. PLUG AT 480' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/07/2017 2:30 PM KCC Agent: HEITH WALSH

Actual Plugging Report:

SET CIBP @ 5910' WITH 2 SX CMT. 1ST PLUG AT 1720' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 480' WITH 50 SX CMT. 3RD PLUG AT 40'-0' WITH 25 SX CMT TO TOP OFF.

Perfs:

Top	Bot	Thru	Comments
5960	5973		

OCT 11 2017
INVOICED
INVOICED
OCT 12 2017

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
SEP 13 2017
KCC DODGE CITY