

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-22516-00-00
Spot: SENWSWNE Sec/Twnshp/Rge: 25-14S-22W
1800 feet from N Section Line, 2150 feet from E Section Line
Lease Name: BISAGNO 'NR' Well #: 2-25
County: TREGO Total Vertical Depth: 4002 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3992		185 SX
SURF	8.625	215		300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/29/2017 10:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: TIM KOHLRUS Company: PINTAIL PETROLEUM, LTD. Phone: (785) 726-1093

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement w/500 # hulls and 19 sx gel.
Port Collar at 1549' w/140 sx cement.
Open hole from 3992' - 4002'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/29/2017 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3840' and pumped 19 sx gel followed by 75 sx cement w/300 # hulls. Pulled tubing to 1700' and pumped 175 sx cement. Cement circulated. Pulled tubing out. Topped off with 30 sx cement. Tied on to backside and squeezed with 10 sx cement. Shut in pressure 75 sx cement.

GPS: 38.80781 -099.71510

Perfs:


INVOICED
OCT 19 2017

Remarks: SWIFT CEMENT TICKET # 30349

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

SEP 07 2017

KCC WICHITA
SEP 28 2017
RECEIVED

Form CP-2/3