

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-195-22400-00-00  
Spot: SENESENW Sec/Twnshp/Rge: 25-14S-22W  
1780 feet from N Section Line, 2490 feet from W Section Line  
Lease Name: BISAGNO NR Well #: 1-25  
County: TREGO Total Vertical Depth: 4121 feet

Operator License No.: 5086  
Op Name: PINTAIL PETROLEUM, LTD.  
Address: 225 N MARKET STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4109		100 SX
SURF	8.625	204		160 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/31/2017 9:00 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: TIM KOHLRUS Company: PINTAIL PETROLEUM, LTD Phone: (785) 726-1093

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement, 600 # hulls and 19 sx gel.  
Port Collar at 1547' w/175 sx cement.  
Perforations: 4002' - 4084'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/31/2017 12:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3840' and pumped 19 sx gel followed by 75 sx cement w/300 # hulls. Pulled tubing to 1700' and pumped 216 sx cement. Cement circulated. Pulled tubing out. Topped off with 10 sx cement. Tied on to backside with 200 psi.

GPS: 38.80781 -099.71789

Perfs:

Top	Bot	Thru	Comments
4002	4010		

INVOICED  
OCT 19 2017

Remarks: SWIFT CEMENT TICKET # 30454

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

CM

KCC WICHITA

SEP 28 2017

RECEIVED

SEP 07 2017

Form CP-2/3