

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-02608-00-00
Spot: SWNWNNW Sec/Twnshp/Rge: 5-24S-17E
620 feet from N Section Line, 1400 feet from W Section Line
Lease Name: WOLF MCADAMS Well #: 7
County: WOODSON Total Vertical Depth: 850 feet

Operator License No.: 30345
Op Name: PIQUA PETRO, INC.
Address: 1331 XYLAN RD.
PIQUA, KS 66761

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	850		0 SX
SURF	7	20		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/18/2017 12:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Revd. from: ADAM SPLECHTER Company: _____ Phone: (620) 468-2681

Proposed Plugging Method: Wash tubing outside 2" casing to 750'7". Mix and pump 40 sks cement. Pull 3/4" to 500', mix and pump 50 sks cement. Pull 3/4" tubing to 300', mix and pump 40 sks cement.

Plugging Proposal Received By: _____ Witness Type: NONE
Date/Time Plugging Completed: 08/25/2017 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Run 3/4" tubing to TD. Washed tubing down outside 2" casing to 750'. Mixed and pumped 40 sacks cement at TD. Pulled 3/4" tubing to 500'. Mixed and pumped 50 sacks cement at 500'. Pulled 3/4" tubing to 300' and mixed and pumped 40 sacks cement at 300'. Bulk truck empty. Pulled 3/4" tubing out of well. Ran 3/4" tubing to 200' and hit cement on outside 2". Pumped and circulated cement to surface. Pulled 3/4" tubing out of hole and topped off annulus w/cement. A total of 130 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED
KCC DIST # 3
SEP 27 2017
CHANUTE, KS

RD

INVOICED
OCT 19 2017

Remarks:

Plugged through: TBG

District: 03

Signed _____

(TECHNICIAN)