

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-207-02607-00-00  
Spot: NWNWENW Sec/Twnshp/Rge: 5-24S-17E  
168 feet from N Section Line, 1475 feet from W Section Line  
Lease Name: WOLF MCADAMS Well #: 6  
County: WOODSON Total Vertical Depth: 900 feet

Operator License No.: 30345  
Op Name: PIQUA PETRO, INC.  
Address: 1331 XYLAN RD  
PIQUA, KS 66761

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	900		0 SX
SURF	7	20		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/25/2017 12:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: ADAM SPLECHTER Company: \_\_\_\_\_ Phone: (620) 468-2681

Proposed Plugging Method: Wash 1" to T.D. Spot 25 sk cement @ TD. Pull 1" to 500'. Fill to surface w/cement. Pull remaining tubing. Squeeze 130 sk cement into well and shut in well.

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: NONE  
Date/Time Plugging Completed: 08/25/2017 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the 2" casing to TD. Casing had been perforated at 500' and 200'. Pumped and placed 25 sacks at TD. Pulled 1" pipe up to 500'. Pumped and circulated cement through the 1" pipe from 500' to surface. Pulled the rest of the 1" pipe out of the casing. Hooked onto the 2" casing and squeezed cement from top to bottom with 130 sacks of cement. A total of 160 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED  
KCC DIST # 3  
SEP 27 2017  
CHANUTE, KS

R.D

INVOICED  
OCT 19 2017

Remarks:

Plugged through: TBG

District: 03

Signed \_\_\_\_\_

(TECHNICIAN)