

State of Kansas



15.159.30041.0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

October 24, 1967

RECEIVED  
MAY 17 1967  
11-17-67  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Great Bend Pipe & Supply Co., Inc.

Complete Address: Drawer "B", Great Bend, Kansas 67530

Lease Name: Schafer "C" Well No. 1

Location: NE SW SE Sec. 2 Twp. 21 Rge. 9 (E) (W) X

County Rice Total Depth 2950' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 2925' and cement with 5 sacks.

Fill hole with mud to 230'. Set rock bridge from 230' to 220' and

cement hole with 20 sacks. Fill hole with mud to 40'. Set rock

bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent