

State of Kansas



15.159.30182.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
CORPORATION COMMISSION

NOV 7 1967

CONSERVATION DIVISION  
October 24, 1967  
Wichita, Kansas

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Great Bend Pipe & Supply Co., Inc.

Complete Address: Drawer "B", Great Bend, Kansas

Lease Name: Schafer "C" Well No. 3

Location: SE SW SE Sec. 2 Twp. 21 Rge. 9 (E) (W) X

County Rice Total Depth 2956' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 2925' and cement with 5 sacks.

Fill hole with mud to 230'. Set rock bridge from 230' to 220' and

cement hole with 20 sacks cement. Fill hole with mud to 40'. Set

rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent