

15.159.30047.0000

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 2 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bradley of Donald C. Slawson has this

date requested permission to plug the following described well:

Mr. Bradley guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson

Complete Address: 408 One Twenty Bldg. Wichita, Kansas

Lease Name: Stewart "B" Well No. # 1

Location: SE SE SW Sec. 2 Twp. 21 Rge. 9 (E) (W)

County Rice Total Depth 3000' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bradley was instructed to plug the well as follows:

8 5/8"-248'-Circulated w/cement. Well log shown.

8 5/8"-165'-Circulated w/cement. 4 1/2"-2999'-Cemented. Top perforations 2944'

Plug set at 2930'. Bridge 2930' to 2920'. 4 Sax. cement 2920' to 2875'

Mud 2875' to 165'. Bridge 165' to 155'. 25 Sax. cement 155' to 80'.

Mud 80' to 40'. Bridge 40' to 30'. 10 Sax. cement 30' to 0.

Very truly yours,

[Signature]
Conservation Division Agent