

State of Kansas



15.159.30057.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
October 24, 1967
STATE CORPORATION COMMISSION
NOV 8 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Great Bend Pipe & Supply Co., Inc.

Complete Address: Drawer "B", Great Bend, Kansas 67530

Lease Name: Schafer "C" Well No. 2

Location: SW SW SE Sec. 2 Twp. 21 Rge. 9 (E) (W) X

County Rice Total Depth 2949' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 2925' and cement with 5 sacks.

Fill hole with mud to 220'. Set rock bridge from 220' to 210' and

cement hole with 20 sacks. Fill hole with mud to 40'. Set rock bridge

from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Richard J. Thomas
Conservation Division Agent