

State of Kansas



15.185.20057.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill,  
filed September 12, 1967.

Dear Sir:

Mr. Clarence Michael of Sage Drilling Co., Inc. has this  
date requested permission to plug the following described well:

Mr. Michael guarantees payment of the plugging fee.

Operator's full Name: George Reed

Complete Address: 1223 Union National Bldg., Wichita, Kansas 67202

Lease Name: De Werff Well No. # 1

Location: SE NE NW Sec. 4 Twp. 21 Rge. 12 (E)(W) W

County Stafford Total Depth 3468' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Michael was instructed to plug the well as follows:

244' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fill  
hole with drilling mud to 235', 1st cementing plug, bridge with 1/2 sack  
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',  
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

STATE CORPORATION COMMISSION  
Very truly yours,

SEP 27 1967

Archie Elving  
Conservation Division Agent

CONSERVATION DIVISION  
Wichita, Kansas