

State of Kansas



15.185.30296.0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 24 1960

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Clarence Michael of Sage Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Michael guarantees payment of the plugging fee.

Operator's full Name: L. K. Parrish

Complete Address: 714 Fourth National Bank Bldg., Wichita, Kansas

Lease Name: Hewitt Well No. # 3

Location: NE SW SW Sec. 4 Twp. 21 Rge. 12 (E)(W) W

County Stafford Total Depth 3520' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Michael was instructed to plug the well as follows:

251' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fill hole with drilling mud to 240', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Audie Elving
Conservation Division Agent