

State of Kansas



FORM - CP-2  
Rev. 9-8-64

15.185.30223.0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B HARVEY Secretary  
E. EDWARD JOHNSON Gen Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

**RECEIVED**  
STATE CORPORATION COMMISSION

SEP 21 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Lowell Moore of C-G Drilling Company has this date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: L. K. Parrish

Complete Address: 714 Fourth National Bank Bldg., Wichita, Ks.

Lease Name: Fred Hewitt Well No. # 1

Location: NW SW SE Sec. 4 Twp. 21 Rge. 12 (E)(W) W

County Stafford Total Depth 3492' Oil Well     

Gas Well      Input Well      SWD Well      D & A       Lost Hole     

Mr. Moore was instructed to plug the well as follows:

254' of 8 5/8" surface pipe, cemented with 350 sacks. Fill hole with drilling mud to 225', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent