

State of Kansas



15.185.20512.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

RECEIVED
STATE CORPORATION COMMISSION
AUG 8 1974
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Zimmerman of Woodman-Iannitti has this
date requested permission to plug the following described well:

Mr. Zimmerman guarantees payment of the plugging fee.

Operator's full Name: Bannister & Carey

Complete Address: 5512 Plaza Lane Wichita, KS

Lease Name: Herb Well No. 1

Location: SW/SE/SE Sec. 15 Twp. 21 Rge. 13 (E)(W) S

County: Stafford Total Depth 3688 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Zimmerman was instructed to plug the well as follows:
289 ft 8 5/8 surface cemented with 225 sacks. Pump plug,
40 sacks cement to 500 ft. 2nd plug at 250 ft, 25 sacks
cement. Mud to 40 ft, plug, 1/2 sack hulls, 15 sacks cement
to surface. 2 sacks cement in rat hole.

Pumped by Sun Cementing Co. Great Bend, KS

Very truly yours,

[Signature]
Conservation Division Agent