

State of Kansas



FORM - CP-2
Rev. 9-8-64

15.185.30035.0000

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

MAR 8 1965

CONSERVATION DIVISION
Wichita, Kansas

3-8-1965

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Earl Dunlap of C-G Drilling Company has this
date requested permission to plug the following described well:

Mr. Dunlap guarantees payment of the plugging fee.

Operator's full Name: George A. Reed

Complete Address: 1301 Union National Bldg., Wichita, Ks.

Lease Name: Hall Well No. # 1

Location: NE NE NW Sec. 15 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3625' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dunlap was instructed to plug the well as follows:

279' of 8 5/8" surface pipe, cement circulated with 250 sacks.
Fill hole with drilling mud to 260', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent