



15-185-19540-0001

JOHN ANDERSON, Jr. Governor  
WILLIAM L MITCHELL Chairman  
ALVIN P. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUN 21 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Lawrence Coats of Virginia Drilling Co. has this date requested permission to plug the following described well:

Mr. Coats guarantees payment of the plugging fee.

Operator's full Name: Virginia Drilling Company, Inc.

Complete Address: 712 Brown Bldg., Wichita, Kansas

Lease Name: Rose Well No. # 7

Location: C SE SE Sec. 22 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3675' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Coats was instructed to plug the well as follows:

281' of 8 5/8" surface pipe, cemented with 150 sacks. Fill hole with drilling mud to 260', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent