



15.185.30274.0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 24 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Clarence Michael of Sage Drilling Company has this date requested permission to plug the following described well:

Mr. Michael guarantees payment of the plugging fee.

Operator's full Name: Circle Oil Company

Complete Address: 500 Bitting Bldg., Wichita, Kansas

Lease Name: Hewitt Well No. # 2

Location: SW SW NW Sec. 22 Twp. 21 Rge. 12 (E)(W) W

County Stafford Total Depth 3715' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Michael was instructed to plug the well as follows:

277' of 8 5/8" surface pipe, cement circulated with 240 sacks.
Fill hole with drilling mud to 250', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent