



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAR 20 1963

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

March 12, 1963.

Dear Sir:

Mr. R. E. Smith of Glenn & Smith Pipe Plg. Co. has this date requested permission to plug the following described well:

Mr. R. E. Smith guarantees payment of the plugging fee.

Operator's full Name: Alpine Oil & Royalty Co., Inc.

Complete Address: 800 Bitting Bldg. Wichita, Kansas.

Lease Name: Bennett #2 Well No. #2

Location: SE-NW-NE Sec. 11 Twp. 21 Rge. 13 (E) (W) X

County Stafford Total Depth 3545' Abandoned Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. R. E. Smith was instructed to plug the well as follows:

3532' of 5 1/2" long string, sanded to 3525' & 3 sacks cement.  
(2440' of 5 1/2" pipe pulled) 225' of 8 5/8" surface pipe circulated  
with 250 sacks cement. Hole filled to 200' with heavy mud,  
10' rock bridge & 20 sacks cement. Hole filled to 40' with  
heavy mud & 10' rock bridge & 10 sacks cement to base of  
cellar.

Very truly yours,

*Harman J.ustus*  
Conservation Division Agent