



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 WICHITA, KANSAS

MAR 15 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

March 3, 1963

CONSERVATION DIVISION
 WICHITA, KANSAS

3-15-1963

Dear Sir:

Mr. R. E. Smith of Glenn & Smith Pipe Pulling Co. has this date requested permission to plug the following described well:

Mr. R. E. Smith guarantees payment of the plugging fee.

Operator's full Name: Alpine Oil & Royalty Co. Inc.

Complete Address: 800 Bitting Bldg. Wichita, Kansas.

Lease Name: Bennett #1 Well No. #1

Location: NW-SW-NE Sec. 11 Twp. 21 Rge. 13 (E) (W)

County Stafford Total Depth 3567' ^{Abandoned} Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. R. E. Smith. was instructed to plug the well as follows:

3567' of 5 1/2" long string plugged back to 3367' Top perforation at 3270'. Sanded to 3260' & 4 sacks cement. 2817' of 5 1/2" pipe pulled. 255' of 8 5/8" surface pipe circulated with cement. Hole filled to 200' with mud, 10' rock bridge & 20 sacks cement. Hole filled to 40' with mud, 10' rock bridge & 10 sacks cement to base of cellar.

Very truly yours,

Harmon J. Austin
 Conservation Division Agent