

15.051.30551.00.00

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
CONSERVATION DIVISION

SEP 25 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Dobbs of E. K. Edmiston has this

date requested permission to plug the following described well:

Mr. Dobbs guarantees payment of the plugging fee.

Operator's full Name: E. K. Edmiston

Complete Address: 425 First Nat'l Bank Bldg. Wichita, Kansas

Lease Name: Brungardt "C" Well No. 2

Location: NW NE NW Sec. 31 Twp. 13 Rge. 16 (E)(W) X

County Ellis Total Depth 3535 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dobbs was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 620' and displace
100 sc cement thru drill pipe. Heavy mud to 150' set cementing plug
and displace 25 sc cement thru drill pipe. Heavy mud to 40' set cem
enting plug, 1/2 sc hulls and 10 sc cement to base of wellar. Plug rat
hole with 2 sc cement.

Very truly yours,

L. F. Massey
Conservation Division Agent