

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

JAN 5 1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum, Inc.,

Complete Address 300 W Douglas Wichita, Kansas

Lease Name Wasinger "F" Well No. 2

Location SE NW NE Sec. 15 Twp. 11 Rge. 18 (E) (W) X

County Ellis Total Depth 3190* 3125

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Garvey Drlg.

Address Wichita, Ks. License No.

Operation Completed: Hour 6:30 P Day 1 Month 1 Year 1968

The above well was plugged as follows:

RTD 3190' 8 5/8 csg set at 1180' cwc 555 sc.
Gunned pits, circulated heavy mud, set cementing plug at 1050' and displaced 70 sc cem.
thru dri pipe. Heavy mud to 300' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/5/68
INV. NO. 7053-W

Signed: Leo J. Massey
Well Plugging Supervisor