



STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 26 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Sohio Petroleum Company

Complete Address P. O. Box 673 Russell, Kansas 67665

Lease Name Bemis "J" Well No. 3

Location E/2 of SE/4 Sec. 33 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3670'

Abandoned Oil Well XX Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Co. Tools

Address \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 1:30 P Day 20 Month 12 Year 1973

The above well was plugged as follows:

- Total Depth 3670' 8 5/8 csg set at 300' owe.
- 5 1/2 csg set at 3658' cw 150 sk cem.
- 5 1/2 csg 2-stage collar set on anhydrite & circ to surface with 500 sk cem.
- No pipe recovered.
- Ran 114 jts tbg set at 3620' -pumped 30 sk gel & water -displaced 25 sk cem.
- Pulled 94 jts tbg set at 618' -pumped 50 sk cem.
- Pulled remaining 20 jts tbg & capped 5 1/2 csg W/15 sk cem.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo R. Massey  
Well Plugging Supervisor

INVOICED

DATE 12/28/73  
INV. NO. 8333-W