

B

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 134-20

LOCATION NE-NE-SW

SEC. 35 TWP. 12 RGE. 20-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease John L. King

Operator Continental Oil Co Address R.F.D. #4 Lyons - Kansas

Field _____ County Ellis

Total Depth 3881 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 8 3/8 - 125 ft. Circulated with cement
5 1/2" casing set at 3780 ft. cemented with 150 sacks cement
Plugged back from bottom to 3720 ft & put in 8 sacks
cement with Murphy Bailor - Ripped off & recovered
2375 ft of 5 1/2" casing - Filled with mud to 200 ft - Plug
& 15 sacks of cement at 200 ft - Surface Plug 25 ft
below the surface & 10 sacks of cement - Filling hole
& surface.*

*Jack Shaw
Pipe Puller & Plugger*

C. M. Stough
District Conservation Agent.

Date 11-26-47

PLUGGING
FILE SEC 35 TWP 12 R 20
COCK PAGE 134 LINE 20

11-29-1947