

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Robinowitz Oil Company

Complete Address: 1322 E. 50th street Tulsa, Oklahoma

Lease Name Weisner Well No. 4

Location NW NW SW Sec. 30 Twp. 12 Rge. 20 (E) (W) X

County Ellis Total Depth 3917

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Omega Drilling Inc.

Address: Wichita, Kansas License No.

Operation Completed: Hour 6 A Day 4 Month 5 Year 1967

The Above well was plugged as follows:

RTD 3917' 8 5/8 csg set at 220' cwc.

Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 20 sc cem.
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

MAY 5 1967

Signed: Leo F. Massey
Well Plugging Supervisor

DATE

5/5/67

INV. NO.

5168-W

CONSERVATION DIVISION
Wichita, Kansas