

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Palomino Petroleum
 Complete Address 304 Insurance Bldg., Wichita, Kansas 67202
 Lease Name Kohl Well No. 1
 Location SW SE SW Sec. 25 Twp. 12 Rge. (E) (W) 20
 County Ellis Total Depth 3875'
 Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated
 Plugging Contractor Pipe Pullers, Inc.
 Address Box 486, Ellinwood, Kansas 67526 License No. 462
 Operation Completed: Hour 11:15 A Day 24 Month 2 Year 1975

The above well was plugged as follows:

Total Depth 3875' 8 5/8 csg set at 207' cwc 175 sk.

4 1/2 csg set at 3871 cw 250 sk cem. & perf. (3496')

Set perm plg at 3050' -poured 20' sand -dumped 4 sk cem W/dump bailer. (3050-3000)

Cutoff & recovered 810' of 4 1/2 csg.

Mixed & pumped down 8 5/8 csg with 20 sk gel & water- 300 lbs hulls- 70 sk 50-50

poz 6% -8 sk gel & water -released plug & 50 sk 50-50 poz 6% by Alliad Cem. Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 3/5/75
INV. NO. 923-W