

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 5 1967CONSERVATION DIVISION
WICHITA, KANSASJ. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Red Onion *a/o Zenith Drilling Corporation*
 Complete Address: Aspen, Colorado *300 W. Douglas Wichita, Kansas 67202*
 Lease Name Kohl Well No. 1
 Location SW SE SW Sec. 25 Twp. 12 Rge. 20 (E) (W) X
 County Ellis Total Depth 3875
 Abandoned Oil Well Gas Well Input Well SWD Well D & A X
 Other well as hereafter indicated:
 Plugging Contractor: Murfin Drlg. Co.,
 Address: Wichita, Kansas License No.
 Operation Completed: Hour 10 P Day 3 Month 12 Year 1967

The Above well was plugged as follows:

RTD 3875' 8 5/8 csg set at 206' cwc.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 100 sc cem.
 thru drill pipe. Heavy mud to 210' set cementing plug and displaced 25 sc cement thru
 drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
 of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. W. 7. Massey
Well Plugging SupervisorDATE 12/5/67
INV. NO. 6845-W